LADIES
New Safety Flooring
Full internal redecoration
GENTS
New Safety Flooring
Full internal redecoration
Replace radiator
BAR AREA
Sand & recoat Timber flooring
New TV in new position
Shelf
New curtain / blinds
New light fittings & bric-a-brac required, new background music system
GAMES AREA
Clean exist tiles
New TV in new position
New carpet tiles
BAR
New Altro
New bottle coolers, 6x doubles, 10x single
Sink & Drainer
LOUNGE
Sand & recoat Timber flooring
New curtain / blinds
Ex Concrete Slab Pavers
Ex'g tiles
GAMES AREA
Ex Timber Effect Flooring
New TV in new position
Remove existing drinks shelf
New timber bar building & decoration with underbar units & shelving
W/C
Ex Safety Flooring
W/C
Ex Tiles
Ex Tiles
LOBBY
New matting
Ex Safety Flooring
Fix Safety Flooring
New upper door to match
Extraction Motor
KITCHEN
Ex Safety Flooring
OFFICE
Allow for new services plus new worktop / chair to form office in kitchen area
No works to kitchen area
STORE
Safety Flooring
Remove existing rubbish and debris
Shelf
Chest Freezer
STORE
Concrete
No works to store area
Fridge
Fridge
Shelf
Shelf
Shelf
CELLAR AREA
- New decorations to cold cellar only
- Retain exisg cellar cooling system
- BWIC as required (Smart dispense to be installed)
Full internal redecoration
BEER CELLAR
Concrete
Beer Cooler
Cellar Fan
Sink
Keg Pumps
Gas
Shelf
Ice Maker
Beer Cooler
Keg Pumps
Cellar Fan
New timber fire escape door & frame to replace uPVC door
YARD AREA
Clear rubbish & debris to yard area.
Concrete
Concrete
Concrete
Tank
New matting
Cupboard
Beer Garden
Remove existing timber shelves
New planting
Remove existing rubbish and debris
Allow to cap off / make safe services as required
UP
DN
New
New HIGH
New H
New MID